

1 090541

4-19

API NUMBER 15- 203-01,002 - 00-03

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C SW NW, SEC. 12, T 20 S, R 36 W/E

1980 feet from NE section line

660 feet from WE section line

Lease Name Dipman Well # 1 OWWO

County Wichita 168.168

Well Total Depth 5190 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 13 3/8 feet 357

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506

Operator: Woolsey Petroleum Corporation

Name & Address 107 N. Market, Ste. 600

Wichita, KS 67202-1807

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 09 1995  
06-710-7925  
WICHITA, KANSAS

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 19 Month: 4 Year: 19 95

Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 4 1/2" at 5139' w/240 sx cement, PBDT 5110', Perfs at 4986-96, 4898-4906', CIBP @ 4960'  
1st plug sand 4 1/2" casing back to 4850' and dump 4 sx cement on top,

2nd plug load hole with gel and spot 80 sx cement at 1200',

3rd plug pull to 600' and spot 50 sx cement,

4th plug pull to 360' and spot 75 sx cement, 5th plug at 40' with 25 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 19 Month: 4 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4850' and dumped 4 sx cement on top of sand through bailer,

2nd plug loaded hole with gel and spotted 80 sx cement at 1200',

3rd plug pulled to 600' and spotted 50 sx cement,

4th plug pulled to 360' and spotted 75 sx cement,

5th plug at 40' with 25 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1200' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

(old / XXXXXX) observe this plugging.

DATE JUN 09 1995

INV. NO. 42925

Signed [Signature] (TECHNICIAN)