

6-15

1 051322

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-203-20,093-00-00

C SW SE, SEC. 11, T 20 S, R 36 W/E

660 feet from S section line

1980 feet from E section line
Steven J.

TECHNICIAN'S PLUGGING REPORT

Operator License # 3819

Lease Name Graff Well # 1

Operator: Diversified Production Service
Name & Address: 8908 S. Yale, Suite 229

County Wichita 165.10

Tulsa, OK 74137

Well Total Depth 5080 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 15 Month: 6 Year: 19 90

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 3156'
Anhydrite 2237-55'
1st plug at 2250' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 50 sx cement, 4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 a.m. Day: 15 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floeal by B.J. Services.
(if additional description is necessary, use BACK of this form.)

INVOICED (XXXX) (did not) observe this plugging.

DATE 6-27-90

INV. NO. 28506

STATE CORPORATION COMMISSION
JUN 21 1990
06-21-1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard M. Lacey
(TECHNICIAN)

EFFECTIVE DATE: 5/8/90

State of Kansas 203-20,093-00-06

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 05 10 90
month day year

... C. SW. SE. Sec. 11. Twp. 20 S, Rg. 36. X East West

OPERATOR: License # 3819
Name: Diversified Production Service
Address: 8908 S. Yale, Suite 229
City/State/Zip: Tulsa, OK 74137
Contact Person: Jack Wilson
Phone: (918) 493-1418

660 feet from South line of Section
1980 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

County: Wichita
Lease Name: Steven J. Graff Well # 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil Inj Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OAWO Disposal Wildcat Cable
 Seismic; # of Holes

Is this a Prorated Field? yes no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 660'
Ground Surface Elevation: Unknown feet MSL
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 1150'
Surface Pipe by Alternate: 1 2 250'
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: None
Projected Total Depth: 5300'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
 well farm pond other
DWR Permit #: Will file
Will Cores Be Taken?: yes no
If yes, proposed zone:

If OAWO: old well information as follows:
Operator: N/A
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes no
If yes, total depth location:

AFFIDAVIT

250' Alt. II Req.

Exp. 11/3/90

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101,

Pusher Bill Wang
TD 5080 FORMATION MIS
SURFACE PIPE 8 5/8" @ 220 CONDUCTOR
ANHYDRITE T- 2221 B-2225 ELEVATION 1156
STARTING TIME 6:00 (AM/PM) DATE 6-15-90
COMPLETION TIME 10:45 (AM/PM) DATE 11
PLUG NO. 1 Arbuckle Plug @ Ft. W/ SX
2 Hug./Council @ Ft. W/ SX
3 Anhydrite Base @ 2250 Ft. W/ 50 SX
2 1-1/2 Base Anyh. @ 1200 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 100 Ft. W/ 50 SX
4 Bottom Surface @ 300 Ft. W/ 50 SX
5 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY DJ Services
TECHNICIAN A.L DATE 6-14-90
TYPE OF CEMENT 60/40 6% 1/4 Flowspec
SPUD DATE 6-4-90 INIT. AW
LENGTH SURFACE PLANNED 250'
RESERVE PIT STATUS- REMOVE FLUID LINED