

1 040853

6-8

API NUMBER 15- 203-20,111-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NW SW, SEC. 3, T 20 S, R 36 W/XX

2310 feet from S section line

660 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506

Lease Name Bernice Smith Well # 1

Operator: Woolsey Petroleum Corporation

County Wichita 188.50

Name & Address 107 N. Market, Ste. 600

Well Total Depth 5800 feet

Wichita, KS 67202-1807

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 7 P.M. Day: 7 Month: 6 Year: 1994

Plugging proposal received from Gary Fisher

(company name) Abercrombie RTD Inc. (phone) 316-262-1841

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2248-62'

1st plug at Hugoton/Council Grove with 100 sx cement, 2nd plug at 2262' with 50 sx cement,

3rd plug at 1250' with 80 sx cement, 4th plug at 600' with 50 sx cement,

5th plug at 240' with 40 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:15 a.m. Day: 8 Month: 6 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 2262' with 50 sx cement, 3rd plug at 1250' with 80 sx cement,

4th plug at 600' with 50 sx cement,

5th plug at 240' with 40 sx cement,

6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floesal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXXX) did not observe this plugging.

DATE 6-22-94

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 40631 AUG 11 1994

6-8

RECEIVED
STATE CORPORATION COMMISSION
JUN 09 1994
06-09-1994
CONSERVATION DIVISION
Wichita, Kansas

EFFECTIVE DATE: 5-16-94
DISTRICT # 5437

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: JUNE 4, 1994
month day year

Spot N2 NW SW Sec 3 Twp 20 S. Rg 36 West

OPERATOR: License # 5506
Name: WOOLSEY PETROLEUM CORPORATION
Address: 107 N MARKET STE 600
City/State/Zip: WICHITA KS 67202-1807
Contact Person: I. WAYNE WOOLSEY
Phone: (316) 267-4379

CONTRACTOR: License #: 30684
Name: ABERGROMBIE RTD. INC.

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec ... Infield XX Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OWSO ... Disposal XX Wildcat ... Cable
... Seismic; ... # of Holes ... Other
if OWSO: old well information as follows: n/a
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes XX, no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 11/16/94

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

111

Pusher Gary Fisher -
SPUD DATE 5-26-94 INIT. SM
LENGTH SURFACE PLANNED 200
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 208' CONDUCTOR
ANHYDRITE T-2298 B-2262 ELEVATION
(4980)
TD 5800 FORMATION MMS
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
1 Hug./Council @ 3000 Ft. W/ 100 SX
2 Anhydrite Base @ 2262 Ft. W/ 50 SX
3 1/2 Base Anyh. @ 1250 Ft. W/ 80 SX
4 1/2, 1/2 Plug @ 600 Ft. W/ 50 SX
5 Bottom Surface @ 240 Ft. W/ 40 SX
6 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRCUM 15SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond X)
TECHNICAL DIVISION DATE 6-3-94 Hauling
TYPE OF CEMENT 440 pps 690 gal - 14 FS.
STARTING TIME 7:00 (AM) DATE 6-7-94
COMPLETION TIME 12:15 (AM) DATE 6-8-94
CEMENT COMPANY ALCO

RECEIVED
WATER WELL DIVISION
TECHNICAL DIVISION
DATE 6-3-94
DATE 6-7-94
DATE 6-8-94