

1100356

TO: STATE CORPORATION COMMISSION

API NUMBER 15-171-20,547-00-00
SW SE NE SEC. 35, T 17 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JANSSEN WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

OPERATOR LICENSE # 7775

WELL TOTAL DEPTH 4565 FEET

OPERATOR: WILTON PETROLEUM, INC.

PRODUCTION CSG: SIZE " FEET

NAME AND 901 KING AVE.

SURFACE CASING: SIZE 8 5/8"@ 230' WITH SX

ADDRESS NYSSA, OR 97913

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 12:00 AM DAY: 03 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920

WERE:

1ST PLUG AT 2300' WITH 50 SX CEMENT, 2ND PLUG AT 1500' WITH 80 SX CEMENT.

3RD PLUG AT 250' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 3:15 AM DAY: 03 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2300' WITH 50 SX CEMENT, 2ND PLUG AT 1500' WITH 80 SX CEMENT. 3RD PLUG AT 250 WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

INVOICED
DATE 6/9/00
TEL. NO. 61859

SIGNED

Gary Winters
(TECHNICIAN)

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 2000

CONSERVATION DIVISION
Wichita, Kansas