

1 030777

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-171-20,352-00-00
SW SW NE, SEC. 34, T 17 S, R 31 W/E
2980 feet from S section line
2300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Hermes "S" Well # 1-A

Operator: Donald C. Slawson
Name & Address 200 Douglas Building
Wichita, KS 67202

County Scott 150.31

Well Total Depth 4625 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Bldg., 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 5 p.m. Day: 17 Month: 1 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2924'
Anhydrite 2274-90'

1st plug at 2400' with 25 sx cement, 2nd plug at 1360' with 75 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 p.m. Day: 17 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,

2nd plug at 1350' with 100 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 21 1987 01-21-87

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I (XXXX) did not observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 1-21-87

INV. NO. 15976

1-17

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date January 7 1987 month day year

API Number 15-171-20,352-00-00

OPERATOR: License # 5181 Name SLAWSON, DONALD C. Address 200 Douglas Building City/State/Zip Wichita, Kansas 67202 Contact Person Bill Horigan Phone (316) 263-3201

SW SW NE Sec 34 Twp 17 S, Rg 31 East X West 2980' Ft. from South Line of Section 2300' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5657 Name SLAWSON DRILLING CO. City/State Wichita, Kansas

Nearest lease or unit boundary line 330' feet County Scott

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO Expl X Wildcat Cable

Lease Name HERMES 'S' Well # 1-A Ground surface elevation 2928' GR. (Seis) feet MSL

Domestic well within 330 feet: yes no Municipal well within one mile: yes no

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

Depth to bottom of fresh water 180' Depth to bottom of usable water 1600'

Surface pipe by Alternate 1-2-X Surface pipe planned to be set 320'

Conductor pipe required Projected Total Depth 4650' feet

Formation Mississippian

I certify that well will comply with K.S.A. 55-101, et seq., plus events by plugging hole to KCC specifications. Western Kansas Date 12/31/86 Signature of Operator or Agent Robert B. Jenkins Title District Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 40

This Authorization Expires 7-1-87 Approved By 12-31-86

1-10-87 Set 320'

SW SW NE Sec 34 Twp 17 S, Rg 31 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 2400' feet depth with 25 sxs of 60/40 Poz w/6% Gel
2nd plug @ 1360' feet depth with 75 sxs of 60/40 Poz w/6% Gel
3rd plug @ 360' feet depth with 40 sxs of 60/40 Poz w/6% Gel
4th plug @ 40' feet depth with 10 sxs of 60/40 Poz w/6% Gel
5th plug @ feet depth with sxs of
(2) Rathole with 10 sxs (b) Mousehole with sxs

397-2821 2502
PUSHER Bob Rowe
TD 4625 FORMATION MISS
SURFACE PIPE 8 7/8 @ 318
ANHYDRITE 2274 ELEVATION 2925
STARTING TIME & DATE 8:00 PM 1-17-87
COMPLETION TIME & DATE 8:00 PM 1-17-87
1st PLUG @ 2280 FT. W/ 50 SX
2nd PLUG @ 1350 FT. W/ 100 SX
3rd PLUG @ 330 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ PLUG - SX
CEMENT COMPANY 6 1/4 Poz 6% gel
TECHNICIAN Will call after Aug.
ACU 1570

STATE CORPORATION COMMISSION

JAN 21 1987

CONSERVATION DIVISION Wichita, Kansas