

To: 1 090115
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-19
API NUMBER 15-171-20,436-0000 90 R

NW NE NW, SEC. 34, T 17 S, R 31 W/E
4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484
Operator: Anderson Energy, Inc.
Name & Address: 200 E. First St., Suite 414
Wichita, KS 67202

Lease Name Hermes Well # 1
County Scott 148.68
Well Total Depth 4575 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X _____

Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 4:30 p.m. Day: 19 Month: 9 Year: 19 91

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2268-85'

1st plug at 2300' with 50 sx cement, 2nd plug at 1475' with 80 sx cement,

3rd plug at 725' with 50 sx cement, 4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30 p.m. Day: 19 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,

2nd plug at 1475' with 80 sx cement,

3rd plug at 725' with 50 sx cement,

4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1991

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(if additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed _____
(TECHNICIAN)

INVOICED
DATE 10-4-91
INV. NO. 33254

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 9-9-91

FORM MUST BE TYPED

DISTRICT # 1

State of Kansas 15-171-20,436-000
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SEAT... Yes No

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 15, 1991
month day year

Spot NW NE NW East
Sec 34 Twp 17 S. Rg 31 West

OPERATOR: License # 6484
Name: Anderson Energy, Inc.
Address: 200 E. First St., Suite 414
City/State/Zip: Wichita, KS 67202
Contact Person:
Phone:

4950 feet from South North line of Section
3630 feet from East West line of Section
IS SECTION REGULAR IRREGULAR

CONTRACTOR: License # 5420
Name: White & Ellis Drilling, Inc.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Scott

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
 Gas ... Storage ... Pool Ext. ... Air Rotary
 OWD ... Disposal ... Wildcat ... Cable
 Seismic; ... # of Holes ... Other
 Other

Lease Name: Hermes Well # 1
Field Name: Manning Twst SW

If OWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Is this a Prorated/Spaced Field? ... yes no
Target Formation(s): LKC

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, true vertical depth:
Bottom Hole Location:

Nearest lease or unit boundary: 320'
Ground Surface Elevation: 2923 feet MSL

Exp. 3/4/92

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Judy w/ w+E
SPUD DATE 9-11-91 INIT. SP
LENGTH SURFACE PLANNED 320' of 85'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 3/4" @ 330 CONDUCTOR
ANHYDRITE T- 2285 B- 2285 ELEVATION
TD 4575 FORMATION Mississipp
RAN PIPE @ SX DV TOOL SX ALT II DONE Y N
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 2300 Ft. W/ 50 SX
1/2 Base Anyh. @ 1475 Ft. W/ 80 SX
1/2, 1/2 Plug @ 725 Ft. W/ 50 SX
Bottom Surface @ 360 Ft. W/ 50 SX
40' Plug @ 60 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond)
TECHNICIAN SM DATE 9-13-91 Hauling
TYPE OF CEMENT 60/40 6B 1/4 1-1/2 port plug
STARTING TIME 4:30 (AM/PM) DATE 9-19-91
COMPLETION TIME 4:30 (AM/PM) DATE 9-19-91
CEMENT COMPANY Filled