

1 070936

4-5

239

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,391-00-00
SE NW NE, SEC. 33, T 17 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

4290 feet from S section line

1650 feet from E section line

Operator: Slawson Exploration Company, Inc.
Name & Address: 20 N. Broadway, Suite 700
Oklahoma City, OK 73102

Lease Name Hermes "Q" Well # 1

County Scott 149.01

Well Total Depth 4585 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementers License Number

Address P.O. Box 31, Russell, KS 67665

Company to plug at: Hour: 11 a.m. Day: 5 Month: 4 Year: 19 91

Plugging proposal received from Ben Shaffer

(company name) Slawson Exploration Company, Inc. (phone) 405-232-0201

were: 4 1/2" at 4586' w/200 sx cement, PBSD 4585', Perfs at 4294-98', 2-staged with 500 sx cement

1st plug pump 400 lbs. hulls and 135 sx cement down 4 1/2",

2nd plug pump down backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:40 a.m. Day: 5 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 135 sx cement down 4 1/2",

Maximum pressure 1200 psi and shut in 1000 psi.

Backside would not take.

RECEIVED STATE CORPORATION COMMISSION

APR 10 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOICED (old / xxxxxx) observe this plugging.

DATE 4-22-91

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 31645