

1 120767

1-16

146 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,451-00-00
SE SE SW, SEC. 28, T 17 S, R 31 W/EX
330 feet from S section line
2310 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988
Operator: Slawson Exploration Co., Inc.
Name & Address: 621 N. Robinson, Ste. 490
Oklahoma City, OK 73102

Lease Name Habiger "Q" Well # 1
County Scott
Well Total Depth 4599 149.46 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 16 Month: 1 Year: 19 93

Plugging proposal received from Ed McKenna
(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2277-2300'
1st plug at 2300' with 50 sx cement, 2nd plug at 1150' with 50 sx cement,
3rd plug at 600' with 50 sx cement, 4th plug at 390' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None
Operations Completed: Hour: 9 p.m. Day: 16 Month: 1 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2300' with 50 sx cement,
2nd plug at 1150' with 50 sx cement,
3rd plug at 600' with 50 sx cement,
4th plug at 390' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
01-21-93
JAN 21 1993
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this report.)

INVOICED

1 (XXXX / did not) observe this plugging.
DATE 2-18-93

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 38388

1-16

EFFECTIVE DATE: 12-28-92

State of Kansas
NOTICE OF INTENTION TO DRILL 171-20,451-00204

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT #
SEAT Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 1 8 93
month day year

Spot
SE SE SW Sec 28 Twp 17S S. Rg 31E East
West

OPERATOR: License # 3988
Name: Slawson Exploration Co., Inc.
Address: 621 N. Robinson, #490
City/State/Zip: Oklahoma City, OK 73102
Contact Person: Steve Slawson
Phone: (405) 232-0201

330 feet from South North line of Section
2310 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Scott
Lease Name: Habiger '0' Well #: 1
Field Name: Wildcat

CONTRACTOR: License #: 60331
Name: Murfin Drilling Co.

Is this a Propped/Spaced Field? yes X no
Target Formation(s): Mississippi
Nearest lease or unit boundary: 330'

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield X Mud Rotary
Gas Storage Pool Ext Air Rotary
OAWD Disposal X Wildcat Cable
Seismic: # of Holes Other

Ground Surface Elevation: 2935 feet MSL
Water well within one-quarter mile: yes no
Public water supply well within one mile: yes X no

If OAWD: old well information as follows:
Operator:
Well Name:
Comp. Dates: Old Total Depth

Depth to bottom of fresh water: 185'
Depth to bottom of usable water: 1,540'
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: (350) 200'

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Length of Conductor pipe required: None
Projected Total Depth: 4600'
Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
X well? farm pond other

Exp. 6/23/93

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well in compliance with K.S.A. 55-101. et. seq.

200' Alt. II Req.
STATE RECEIVED
CORPORATION COMMISSION

Pusher Ed Mc Kenna
SPUD DATE 1-6-93 INIT. OR

LENGTH SURFACE PLANNED 360

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 3 5/8 CONDUCTOR
ANHYDRITE T-2272 B-2300 ELEVATION
4000' 4000'

RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX Y N
Hug./Council @ 2100 Ft. W/ SX
Anhydrite Base @ 2300 Ft. W/ 50 SX
1/2 Base Anyh. @ 1150 Ft. W/ 50 SX
1/2, 1/2 Plug @ 600 Ft. W/ 50 SX
Bottom Surface @ 390 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX

JAN 21 1993
CONSERVATION DIVISION
WICHITA, KANSAS

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well) Pond
TECHNICIAN OR DATE 1-15-93 Hauling

TYPE OF CEMENT 60-40-10 70 4" floored
STARTING TIME 2: (AM/PM) DATE 1-16-93
COMPLETION TIME 9: (AM/PM) DATE 1-16-93
EMENT COMPANY Allud