

1 070619

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,334-00-00

C NW NE, SEC. 28, T 17 S, R 31 W/E

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Janssen "R" Well # 1

Operator: L.D. Drilling, Inc.

RECEIVED
STATE CORPORATION COMMISSION
12-05-88
DEC 5 1988
CONSERVATION DIVISION
Wichita, Kansas

County Scott

Name &

Address RR 1, Box 183B

Well Total Depth 4625 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc.

License Number 6039

Address RR 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 1:15 p.m. Day: 29 Month: 11 Year: 1988

Plugging proposal received from Mike Kasselmann

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: 4 1/2" at 4624' PBD 4290' Perfs at 4223-4290'

1st plug pump 4 sx hulls, 50 sx cement, 15 sx gel, 1 sx hulls, release plug and pump

150 sx cement,

2nd plug pump 50 sx cement on annulus.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 29 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls, 50 sx cement, 15 sx gel, 100 lbs. hulls, released wiper plug and pumped 35 sx cement. Maximum pressure 1500 psi and shut in 1000 psi.

2nd plug pumped 18 sx cement down 8 5/8", pressured to 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Dan Johnson
(TECHNICIAN)

DATE DEC 8 1988

INV. NO. 23265