

1031540

TO: STATE CORPORATION COMMISSION

API NUMBER 15-171-20,543-0800
110'S NW NE SE SEC. 26, T 17 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 2200 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BROWER WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT 149.50

OPERATOR LICENSE # 5135

WELL TOTAL DEPTH 4600 FEET

OPERATOR: JOHN O FARMER, INC. PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 352 SURFACE CASING: SIZE 8 5/8" @ 220.85' WITH SX

ADDRESS RUSSELL, KS 67665

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 2:00 AM DAY: 14 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920 RECEIVED STATE CORPORATION COMMISSION

WERE:

1ST PLUG AT 2290' WITH 50 SX CEMENT, 2ND PLUG AT 1500' WITH 80 SX CEMENT. FEB 18 2000

3RD PLUG AT 690' WITH 30 SX CEMENT, 4TH PLUG AT 240' WITH 40 SX CEMENT. CONSERVATION DIVISION Wichita, Kansas

5TH PLUG AT 0-40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 4:30 AM DAY: 14 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2290' WITH 50 SX CEMENT, 2ND PLUG AT 1500' WITH 80 SX CEMENT,

3RD PLUG AT 690' WITH 30 SX CEMENT, 4TH PLUG AT 240' WITH 40 SX CEMENT.

5TH PLUG AT 0-40' WITH 10 SX CEMENT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/2# FLO SEAL BY ALLIED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED Steve Durrant (TECHNICIAN) FORM CP-2/3
2/18/00
06/26/99

(R)