

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01753-00-00
Spot: N2NESE Sec/Twnshp/Rge: 14-10S-21W
2310 feet from S Section Line, 660 feet from E Section Line
Lease Name: ACHESON Well #: 5
County: GRAHAM Total Vertical Depth: 3778 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	418	0	w/200 sxs cmt
PROD	5.5	3768	0	w/250 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2011 10:00 AM
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC
Proposal Rcvd. from: JOE BERENS Company: OUTLAW WELL SERVICE LLC Phone: (785) 650-2399

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 400# hulls - 8 sxs gel spacer.
Shoot perfs at 875' and 470'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2011 3:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Shot perfs at 875' and 470'.
Ran tubing to 3028' - pumped 8 sxs gel - followed with 100 sxs cement.
Pulled tubing to 1850' - pumped 320 sxs cement - circulated out the casing and backside.
Tied onto 5 1/2" - squeezed with 20 sxs cement.
S.I.P. 150#.

KCC Control Number: #20100061-002


Remarks: S.O.S. CEMENTING COMPANY-TICKET #538.

Plugged through: TBG

RECEIVED
OCT 20 2011
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

OCT 17 2011