

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24539-00-01
Spot: NWNENW Sec/Twnshp/Rge: 31-19S-12W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HARRIS TRUST Well #: 1
County: BARTON Total Vertical Depth: 3460 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3370		
SURF	8.625	332	0	175 SX
PROD	5.5	3455	1620	140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

RECEIVED
DEC 29 2011
KCC WICHITA

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sand off perms and topped with 5 sxs cement.
Cut casing at 1620' - pulled to 1500' and pumped 150 sxs cement with 300# hulls.
Pulled casing to 600' - pumped 60 sxs cement with 100# hulls.
Pulled to 200' - pumped 100 sxs cement to circulate cement to surface.
Pulled casing - topped off with 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3388	3392		ARBUCKLE
3381	3384		ARBUCKLE
3344	3354		CONG

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

✓ 12/30/11

DEC 27 2011