

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19358-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 21-11S-15W  
330 feet from N Section Line, 330 feet from W Section Line  
Lease Name: SPICER Well #: 1  
County: RUSSELL Total Vertical Depth: 3356 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2011 2:00 PM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 650 sxs 60/40 pozmix - 4% gel - 1500# hulls.  
Washed down to bridge at 1940'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/09/2011 5:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Tubing at 1925' - pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.  
Pulled tubing to 1500' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 975' - pumped 100 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled tubing to 650' - pumped 100 sxs 60/40 pozmix - 4% gel with 400# hulls.  
Pulled tubing to 400' - pumped 300 sxs 60/40 pozmix - 4% gel with 300# hulls.  
Pulled all tubing. Operator will run in and tag cement.  
Tagged cement at 80' from surface.

RECEIVED  
DEC 23 2011  
12-23-11  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38214.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

DEC 15 2011

12/30/11