

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22613-00-00
Spot: SESENW Sec/Twnshp/Rge: 18-11S-24W
2200 feet from N Section Line, 2012 feet from W Section Line
Lease Name: NEWMAN NW Well #: 18-1
County: TREGO Total Vertical Depth: 4320 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		
SURF	8.625	215	0	165 SX
T1	2.375	4316		
PROD	5.5	4301	0	225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2011 10:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DONALD A BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 200# hulls.
DV Tool 2206' w/225 sxs.
Retrieval plug cemented in at 3910'.
Fish in the hole at 3680'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2011 12:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3410' - pumped 7 sxs gel followed with 50 sxs cement with 100# hulls.
Pulled tubing to 2220' - pumped 150 sxs cement - good circulation of cement.
Pulled tubing out - topped off casing with 40 sxs cement - full.
Tied onto backside - full.

Perfs:

Top	Bot	Thru	Comments
4232	4235		CHEROKEE SHAL
3992	3994		KS
3965	3968		
3945	3948		KC
3926	3929		KC

RECEIVED
DEC 23 2011
12:23-11
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #36056.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

CM

DEC 15 2011

✓ 12/30/11