

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22131-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 18-7S-17W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: GEORGE COLBURN Well #: 4
County: ROOKS Total Vertical Depth: 3329 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1260	0	w/475 sxs cmt
COND	13.37	118	0	w/150 sxs cmt
PROD	5.5	3323	0	w/150 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2011 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RICK POPP Company: CASTELLI EXPLORATION, INC. Phone: (405) 722-5511

Proposed Plugging Method: Ordered 470 sxs 60/40 pozmix - 4% gel.
Junk in the hole at 2143'. Tried overshot, washover pipe etc. for two weeks - could not get down.
Perforated at 1260'.
Squeezed at 2129' w/150 sxs; 1834' w/100 sxs.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2011 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2120' - pumped 165 sxs 60/40 pozmix - 4% gel - circulated to surface.
Pulled all tubing Hooked to 5 1/2" casing - pumped 35 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 700#. S.I.P. 650#.
Hooked to 8 5/8" x 5 1/2" annulus. Pressured to 300# immediately.

Perfs:

RECEIVED
DEC 23 2011
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #098.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

✓ 12/30/11

DEC 21 2011