

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22161-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 31-18S-30W
545 feet from S Section Line, 630 feet from E Section Line
Lease Name: WHITING Well #: 2-31
County: LANE Total Vertical Depth: 4642 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4510		WITH 2 SX CMT
SURF	8.625	255		WITH 175 SX CMT
PC		2164		CEMENTED WITH 240 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	4.5	4637	0	WITH 465 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2011 9:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 793-2168

Proposed
Plugging
Method:

PUMP CMT TOP TO BOTTOM & USE 200# HULLS ON BOTTOM. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2011 12:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4510' WITH 2 SX CMT. RUN TBG TO 2200' & PUMPED 170 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 30 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4560	4564		JOHNSON ZONE

RECEIVED
DEC 23 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01
RECEIVED
DEC 12 2011
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)
12/30/11
Form CP-2/3