

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22724-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 24-31S-13W  
330 feet from N Section Line, 990 feet from W Section Line  
Lease Name: PACKARD 4-23 Well #: 1-24  
County: BARBER Total Vertical Depth: 4584 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	217		WITH 165 SX CMT
PROD	4.5	4574	3200	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/15/2011 9:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: SAND BACK TO 4170' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2011 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4150' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. RIP 4 1/2" CASING LOOSE AT 3200'. PULLED CASING UP HOLE TO 2780'. WELL BLEW OUT. 1ST PLUG AT 2780' WITH 50 SX CMT. 2ND PLUG AT 620' WITH 10 SX GEL & 50 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4221	4226		MISSISSIPPI

RECEIVED  
DEC 23 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.


Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
DEC 21 2011  
KCC DODGE CITY

  
12/30/11