

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21671-00-00

Spot: NENWNW <sup>S</sup> Sec/Twnshp/Rge: 13-22S-12W

5028 ~~307~~ feet from N Section Line, 4299 feet from E Section Line

Lease Name: SIEFKES B

Well #: 1

County: STAFFORD

Total Vertical Depth: 3623 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 361        |             | WITH 250 SX CMT |
| PROD   | 5.5   | 3617       | 1424        | WITH 110 SX CMT |

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/19/2011 12:00 PM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: RICHARD LACEY

Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 3240' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/19/2011 1:30 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3200' WITH 5 SX CMT ON TOP OF SAND WITH DUMP BAILER. 1ST PLUG AT 594' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 399' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3616 | 3623 |      |          |

RECEIVED  
MAY 24 2011  
KCC WICHITA

Remarks: \*\*KCC CONTROL NUMBER: 20110066-0001\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed

*Richard W. Lacey*

(TECHNICIAN)

RECEIVED  
MAY 20 2011  
KCC DODGE CITY