

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22435-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 13-22S-12W
2990 feet from S Section Line, 1870 feet from E Section Line
Lease Name: WILLINGER Well #: 1
County: STAFFORD Total Vertical Depth: 3623 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	234		WITH 140 SX CMT
PROD	5.5	3621	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/20/2011 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: WELL APPARENTLY HAS A CASING LEAK. (HIGH FLUID LEVEL) BOTTOM PLUG: RUN TBG TO 3200'. PUMP 10 SX GEL - 50 SX CMT WITH 100# HULLS MIXED IN & DISPLACED TO 3000'. TOP PLUG: PERFORATE 5 1/2" @ 600'. RUN TBG TO 608'. PUMP CMT UNTIL IT CIRCUALTES UP 8 5/8" X 5 1/2" ANNULUS AND 5 1/2" CASING. PULL TBG OUT & TOP OFF HOLE WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2011 9:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFORATE CASING AT 600'. BOTTOM PLUG: RUN TBG TO 3206'. SPOTTED 10 SX GEL & 50 SX CMT W/100# HULLS MIXED IN. PULLED TBG UP TO 602' FOR TOP PLUG. TOP PLUG: PUMPED DOWN TBG W/300 SX CMT. ESTABLISHED GOOD TO NO RETURNS UP 8 5/8" X 5 1/2" ANNULUS & 2 3/8" X 5 1/2" ANNULUS. DID NOT CIRCULATE CMT. WELL ON VACUUM. SHUT DOWN OVER WEEKEND TO LET CMT SET. 5/23/11: TAGGED CMT AT 315' WITH TBG. PULLED TBG TO 284' AND CIRCULATED CMT TO SURFACE WITH 30 SX CMT. PULLED TBG & TOPPED OFF 5 1/2" WITH 5 SX CMT. PUMPED 100 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PUMP PRESSURE 350 PSIG. INITIAL SHUT IN PRESSURE 200 PSIG.

Perfs:

Top	Bot	Thru	Comments
3621	3623	OH	

Remarks: **KCC CONTROL NUMBER: 20110066-002** USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

MAY 26 2011

KCC DODGE CITY

RECEIVED

MAY 31 2011

Form CP-2/3

KCC WICHITA