

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-21715-00-00  
Spot: NESENW Sec/Twnshp/Rge: 24-22S-13W  
3610 feet from S Section Line, 3023 feet from E Section Line  
Lease Name: FISCHER Well #: 1  
County: STAFFORD Total Vertical Depth: 3842 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	300		
PROD	5.5	3767	1759	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/18/2011 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND TO 3630' & 5 SX CMT ON TOP OF SAND. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/18/2011 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3620' & 5 SX CMT ON TOP OF SAND WITH A DUMP BAILER. 1ST PLUG AT 1648' WITH 10 SX GEL & 50 SX CMT. (ADDED PLUG TO STOP OIL FLOW UP 5 1/2" DUE TO HEAVY MUD U-TUBING.) 2ND PLUG AT 749' WITH 50 SX CMT. 3RD PLUG AT 351' WITH 50 SX CMT. 4TH PLUG AT 37' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3688	3706		

Remarks: \*\*KCC CONTROL NUMBER: 20110066-003\*\* USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
MAY 20 2011  
KCC DODGE CITY

RECEIVED  
MAY 24 2011  
KCC WICHITA

Form CP-2/3

*Handwritten signature*