

15-071-20053-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dorchester Exploration, Incorporated,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Wineinger Well No. A-1

Location CNE/4 Sec. 34 Twp. 19 Rge. (E) (W) 40

County Greeley Total Depth 2950'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No.       

Operation Completed: Hour 5:00 AM Day 13 Month 3 Year 1974

The above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 875'.

Circulated hole with heavy mud. Pulled DP to 1100' and displaced 110 Cu. Ft. cement  
thru DP from 1100' to 775'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru  
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

**INVOICED**  
I hereby certify that the above well was plugged as herein stated.  
DATE 3/20/74  
INV. NO. 8773-W  
Signed: N. L. Dichele  
Well Plugging Supervisor