

15-071-20031-00-00

[Signature]
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dorchester Exploration, Inc.

Complete Address 1204 Vaughn Bldg., Midland, Texas 79701

Lease Name Wear Well No. 1-A

Location CNE Sec. 31 Twp. 19 Rge. (E) (W) 40

County Greely Total Depth 2965'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address 620 S. Lincoln, Liberal, Kansas License No. 511

Operation Completed: Hour 12N Day 17 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 2965' 8 5/8 csg set at 233' cwc 150 sk.

4 1/2 csg set at 2964' ew 250 sk.

4 1/2 csg FBTD 2953' with perf. (2925'-2936')

Pumped down 4 1/2 csg with 15 sk cem W/100 lbs hulls. Top of cement 2825'.

Cutoff and recovered 1630' of 4 1/2 csg.

Pulled 4 1/2 csg to 283' -circulated gel & displaced 35 sk cem. (283'-183')

Pulled 4 1/2 csg -filled with gel & water to 33'.

Set rock bridge & filled with 10 sk cement (33'-3')

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 8/20/74
INV. NO. 9740-W