

15-071-20027-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Worcester Exploration, Incorporated,

Complete Address 1201 Vaughn Building, Midland, Texas,

Lease Name Vogleman Well No. 1

Location CSE/4 Sec. 8 Twp. 19 Rge. (E) (W) 10

County Greeley Total Depth 2953'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated THIS WELL WAS DRILLED AS A GAS WELL BY WORCESTER EXPLORATION INC. - NOT TO BE COLLECTED.

Plugging Contractor Patrick Well Service

Address Liberal, Kansas. License No. 650

Operation Completed: Hour 11:00 PM Day 23 Month 10 Year 1973

The above well was plugged as follows:

351'--10 3/4" Surface casing, cement circulated with 300 Sx. (7 7/8" Hole Calibrated)/
2938'--7 1/2" Production casing cemented on bottom with 150 Sx. part. from 2900' to
2924'. Squeezed with 350 Sx. cement. Hole deepened to 2953' with open hole completion.

Pumped 25 Cu. Ft. 50/50 Poz-Lix to 2060' followed by plug. Shot 1 1/2" casing (Dialox)

9 1/2". Pulled 10' joint and spotted 140 Cu. Ft. cement from 2930' to 2951'. Spotted

1 1/2" casing to 370' and displaced 45 Cu. Ft. cement thru 1 1/2". pulled 1 1/2" casing, set

bridge 25' with sack hulls and filled Surface to bottom of cellar with cement.

I hereby certify that the above well was plugged as herein stated.

DATE 10/25/73

Signed: K. L. D. [Signature]
Well Plugging Supervisor

INV. NO. 8061-4