

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Pierce-Dehlinger,

Complete Address 201 V & J Towers, Midland, Texas.

Lease Name A. G. Fecht Well No. 1

Location CNE-SW, 1980' FWL & 1980' FSL of Sec. 3 Twp. 19 Rge. (E) (W) 40

County Greely Total Depth 5460'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No.         

Operation Completed: Hour 12:15 AM Day 22 Month 12 Year 1971

The above well was plugged as follows:

400'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement  
thru DP from 1175' to 850'. Pulled DP to 435' and displaced 30 Cu. Ft. cement thru  
DP from 435' to 360'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Trebet  
Well Plugging Supervisor

1-10-72  
4921-W