

15-071-20008-00-01



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

DEC 17 1973  
12-17-73  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Dorchester Exploration, Incorporated,

Complete Address 1204 Vaughn Building, Midland, Texas.

Lease Name Fecht Well No. 1

Location NE-SW Sec. 3 Twp. 19 Rge. (E) (W) 40

County Greeley Total Depth 1568'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated This well was an attempted wash-down. Bit left bore-hole at top of previously set plug and it was elected to abandon.

Plugging Contractor Sterling Drilling Company,

Address Box #129, Sterling, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:00 PM Day 12 Month 12 Year 1973

The above well was plugged as follows:

405'--R 5/8" Surface casing, cement circulated.  
Top of Dakota section 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement thru DP from 1175' to 850'. Pulled DP to 435' and displaced 30 Cu. Ft. cement thru DP from 435' to 360'. Pulled DP, set bridge 40' with sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. DeKob  
Well Plugging Supervisor

DATE 12/17/73  
INV. NO. 8300-W