

15-071-20004-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Brooks Hall Oil Corporation,

Complete Address: 1710 Liberty Bank Building, Oklahoma City, Oklahoma.

Lease Name Thompson Well No. 1

Location CNE-4 Sec. 28 Twp. 19 Rge. (E) (W) 40

County Greeley Total Depth 5405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Service Drilling Company,

Address: 406 So. Boulder, Tulsa, Oklahoma. License No. _____

Operation Completed: Hour 1:00PM Day 1 Month 9 Year 1968

The Above well was plugged as follows:

403'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 125 Sx. cement thru
DP from 1175' to 602'. Pulled DP to 420' and displaced 25 Sx. cement thru DP from
420' to 315'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/4/68
INV. NO. 8405-W