

15-071-20060-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

AUG 20 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Derchester Exploration, Inc.

Complete Address 1204 Vaughn Bldg., Midland, Texas 79701

Lease Name Sandow Well No. 1

Location CNE Sec. 32 Twp. 19 Rge. (E) (W) 41

County Greely Total Depth 2959'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent Casing Pulling

Address 620 S. Lincoln, Liberal, Kansas License No. 511

Operation Completed: Hour 6P Day 15 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 2950' 8 5/8 csg set at 231' ewe 150 sk.

4 1/2 csg set at 2949' ew 200 sk cmt.

4 1/2 csg PBTD 2925' & perf. (2884-2898)

Pumped down 4 1/2 csg W/15 sk cem. & 1 hull. Top of cement 2784'.

Cutoff & recovered 1216' of 4 1/2 csg.

Set 35 sk cem. plug (300-200) thru 4 1/2 csg.

Gel & water (200-33')

Reek bridge at 33' & filled to surface with 10 sk cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 8/20/74
INV. NO. 9739-W