

15-071-20020-00-60

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dorchester Exploration Company,  
Complete Address 1204 Vaughn Building, Midland, Texas. 79401  
Lease Name Campbell Well No. 1  
Location CSE Sec. 13 Twp. 19 Rge. (E) (W) 41  
County Greeley Total Depth 2930'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Sterling Drilling Company,  
Address Box #129, Sterling, Kansas. License No.         
Operation Completed: Hour 11:00 PM Day 29 Month 1 Year 1973

The above well was plugged as follows:

364'--10 3/4" Surface casing, cement circulated with 300 Sx. (9" Hole).  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 140 Cu. Ft. cement  
thru DP from 1240' to 925'. Pulled DP to 400' and displaced 40 Cu. Ft. cement thru  
DP from 400' to 325'. Pulled DP, set bridge @ 40' with 1 sack hulls and 20 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. G. D. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 2/5/73  
INV. NO. 6940-W