

15-171-00059-00.01

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 17-8

LOCATION CNE-11W-SF

SEC. 25 TWP. 18 RGE. 33-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Harris-"A"

Operator Shallow Water Refining Co. Address 7114 W. Pine - Garden City - Kans

Field _____ County Scott

Total Depth 4948 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 290 ft. Circulated with cement.
5 1/2" casing set at 4783 ft. Cemented with 75 sacks of cement -
Zone Well Plug at 4600 ft. - Plugged back with mud to 4600 ft
Set Rock Bridge & 5 sacks of cement at 4600 ft - Shot off & pulled
the 5 1/2" casing - Filled with mud to 170 ft - Set Rock
Bridge & 20 sacks of cement at 170 ft - Mud
to 60 ft - Bridge & 10 sacks of cement at the surface
A & L. Pipe Pulling Co. - Plugging Contractors

PLUGGING
FILE SEC 25 T 18 R 33W
BOOK PAGE 17 LINE 8

RECEIVED
OCT 4 - 1950
STATE CORPORATION COMMISSION

District Conservation Agent

Date 10-6-50