

To: 1080138 7-25
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-071-20,074-00-00
C NW NW, SEC. 36, T 19 S, R 40 W/2
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 31709
Operator: W.R. Williams
Name & Address
P.O. Box 15163
Amarillo, TX 79105

Lease Name Toadvine Well / 1
County Greeley 96.85
Well Total Depth 2980 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 229

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 9 a.m. Day: 25 Month: 7 Year: 19 97

Plugging proposal received from W.R. Williams
(company name) W.R. Williams (phone) 806-374-4555

were: 4 1/2" at 2980' w/200 sx cement, PBTD 2950', Perfs at 2846-54'
1st plug run tubing to 2780', pump 50 lbs. hulls, 25 sx cement with 50 lbs. hulls mixed in,
pull tubing, 2nd plug perforate at 1400' and pump 80 sx cement, 07-29-97
3rd plug shoot casing, run tubing to 700' and pump 50 sx cement,
4th plug pull tubing to 250', pump 50 sx cement, 5th plug pull tubing to 40' and pump 10 sx cement

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 25 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug Patricks Well Service ran 2 3/8" tubing to 2780' and

Allied pumped 50 lbs. hulls and 25 sx cement with 50 lbs. hulls mixed in. Displaced to
2700'. Pulled tubing. Peak Wireline Service ran free point on 4 1/2" casing. Free point at
1050'. Perforated at 1400', 2nd plug pumped 80 sx cement, displaced to 1200'.
Maximum pressure 900 psi and shut in 50 psi. Flowed back 3 1/2 bbls. Peak Wireline shot casing

at 1000', pulled casing. 3rd plug ran tubing to 700' and pumped 50 sx cement, 4th plug pulled
tubing up to 250' and pumped 50 sx cement, 5th plug pulled to 40' and pumped 10 sx cement.
Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1000' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

1. **INVOICED** Observe this plugging.

Signed Kevin D Strube
(TECHNICIAN)

DATE JUL 30 1997
WV. NO. 48699