

1080244

TO: STATE CORPORATION COMMISSION

4-2

API NUMBER 15-071-20,285-00-00
C NW SEC. 29, T 19 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 3960 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3960 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME KS AGRICULTURAL UNIT WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 155.06

OPERATOR LICENSE # 30606

WELL TOTAL DEPTH 4771 FEET

OPERATOR: MURFIN DRILLING, CO

PRODUCTION CSG: SIZE 5 1/2" AT 4771' WITH 625 SX

NAME AND 250 N WATER, SUITE 300

SURFACE CASING: SIZE 8 5/8" AT 1285' WITH 475 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING, CO

LICENSE NUMBER 30606

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 02 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KEVIN AXELSON

(COMPANY NAME) MURFIN DRILLING (PHONE) 316-267-3241

WERE: PERFS AT 2892' TO 2971' CIBP @ 3050'

1ST PLUG RUN TUBING TO 2822'. PUMP 100# HULLS WITH 200# HULLS MIXED IN 25 SX CEMENT.

2ND PLUG PULLED TUBING TO 1427' PUMPED 175 SX CEMENT CIRCULATED TO SURFACE, PULLED TUBING

OUT OF HOLE. 3RD PLUG PUMPED DOWN 8 5/8" X 5 1/2" ANNULAS 110 SX CEMENT. MAXIMUM PSI @ 200#.

HOLE STAYED LOADED. 4TH PLUG TOPPED OFF 5 1/2" WITH 25 SX CEMENT. HOLE STAYED LOADED.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 02 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG MURFIN RAN TUBING TO 2822'. ACID SERVICES, LLC PUMPED 100# HULLS WITH 200# HULLS

MIXED IN 25 SX CEMENT. 2ND PLUG PULLED TUBING TO 1427' PUMPED 175 SX CEMENT, CIRCULATED

TO SURFACE. PULLED TUBING OUT OF HOLE. 3RD PLUG PUMPED DOWN 8 5/8" X 5 1/2" ANNULAS 110 SX

CEMENT. MAXIMUM PSI @ 200#. HOLE STAYED LOADED. 4TH PLUG TOPPED OFF 5 1/2" WITH 25 SX

CEMENT. HOLE STAYED LOADED.

REMARKS: USED 60/40 POZMIX BY ACID SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. RECEIVED

INVOICED

STATE OF KANSAS SIGNED

Kevin D. Strube (TECHNICIAN)

FORM CP-2/3

DATE 4-28-99

APR 22 1999

INV. NO. 60888

04-22-99 CONSERVATION DIVISION Wichita, Kansas