

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20637-01-00
Spot: CSWNENE Sec/Twnshp/Rge: 7-19S-40W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: KOCH Well Number: 2-H
County: GREELEY Total Vertical Depth: 2917 feet

Operator License No.: 31709
Op Name: WILLIAMS W.R.
Address: PO BOX 15163
AMARILLO, TX 79105

Conductor Pipe: Size 13.375 feet: 242
Surface Casing: Size 9.625 feet: 2520 WITH 850 SX CMT
Production: Size 5.5 feet: 2955 WITH 125 SX CMT
Liner: Size feet: 94.80

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/19/2001 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: WR WILLIAMS Phone: (806) 374-4555

Proposed Plugging Method: SET CIBP @ 2900', SHOOT OFF 5-1/2" @ +/- 2000', 80 SX @ 1500', 50 SX @ 750', 50 SX @ 300', 15 SX @ 40'.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/19/2001 3:15 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

2955-3833' OPEN HOLE LATERAL. SET CIBP @ 2900' WITH 2 SX CMT ON TOP. 1ST PLUG PULLED UP TO 1500' & PUMPED 50 SX CMT. 2ND PLUG PULLED UP TO 750' & PUMPED 50 SX CMT. 3RD PLUG PULLED UP TO 300' & PUMPED 50 SX CMT. 4TH PLUG PULLED UP TO 40' & PUMPED 15 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2016' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Kevin Strube

(TECHNICIAN)

SEP 24 2001

Form CP-2/3

RECEIVED

SEP 25 2001

09-25-01

INVOICED

DATE 9-25-01

INV. NO. 2002060616

NP