

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20596-00-00
Spot: CNE Sec/Twnshp/Rge: 4-19S-40W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease/Unit Name: RICHMOND Well Number: 2-4
County: GREELEY Total Vertical Depth: 2985 feet

Operator License No.: 32340
Op Name: BLUEGRASS ENERGY, INC.
Address: 5727 S. LEWIS, STE 720
TULSA, OK 74105

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 282 WITH 200 SX CMT
Production: Size 4.5 feet: 2984 WITH 700 SX CMT
Liner: Size _____ feet: \$ 97.01

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/23/2001 9:45 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE OLSON Company: BLUEGRASS ENERGY Phone: (316) 376-8190

Proposed Plugging Method: PUMP 400# HULLS & CMT TO SURFACE. USE 50 SX CMT TO CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/23/2001 10:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2907'. RETAINER AT 2907'. PERFS AT 2890-96'. PUMPED DOWN 4 1/2" CASING 400# HULLS & 135 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN WITH 600#. PUMPED DOWN 8 5/8" X 4 1/2" PUMPED 25 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 400#.

KANSAS CORP
AUG 02 10 08-02-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

INVOICED
DATE 8-3-01
NO. 2002060166

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

JUL 31 2001

Form 1023

MP