

1 070579

15-07-20054-0000

API NUMBER 15- Drill Completion Date 3/74

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW/4, SEC. 24, T 19 S, R 40 W/X
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9922

Lease Name Floyd Well # 1 A

Operator: Hughes Seewald
Name & Address % Higginbottom Eng., Inc.
P.O. Box 2587
Liberal, KS 67905

County Greeley
Well Total Depth 2899 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497
Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 24 Month: 8 Year: 19 88

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 2877' PBD 2876' Perfs at 2826-37' Squeezed at 1700' with 200 sx cement

1st plug pump 2 sx hulls and 20 sx of common cement to bottom,

2nd plug pump 40 sx cement at stub,

3rd plug pump 40 sx cement at 270',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 24 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 20 sx common cement,

2nd plug spot through casing 40 sx cement at 1040',

3rd plug 40 sx cement at 270',

4th plug 8 sx cement at 40'.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 1046' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

JUL 03 1991

FORM CP-2/3 Rev. 01-84

CONSERVATION DIVISION Wichita, Kansas