

1080280

TO: STATE CORPORATION COMMISSION

API NUMBER 15-071-20,044-00-00
C NW SEC. 24, T 19 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME COUPLAND WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY GREELEY 95.88

OPERATOR LICENSE # 32340 10/25

WELL TOTAL DEPTH 2950 FEET

OPERATOR: BLUEGRASS ENERGY INC.

PRODUCTION CSG: SIZE 4 1/2" @ 2950' WITH 750 SX

NAME AND 5727 S LEWIS, SUITE 260

SURFACE CASING: SIZE 8 5/8" @ 233' WITH 200 SX

ADDRESS TULSA, OK 74105

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 25 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DAVE OLSON

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: PERFS AT 2866-2920

PUMP DOWN 4 1/2" CASING 300# HULLS AND 185 SX CEMENT. MAXIMUM PRESSURE AT 600#. SHUT IN AT

500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CEMENT. PRESSURE UP TO 300# AND SHUT IN.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 11:00 AM DAY: 25 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT _____

SWIFT SERVICES PUMPED DOWN 4 1/2" CASING 300# HULLS AND 185 SX CEMENT. MAXIMUM PSI AT 600#.

SHUT IN WITH 500#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CEMENT. PRESSURED UP TO 300#

AND SHUT IN.

11-2-99

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

DATE 12/3

SIGNED Kevin D Strube

INV. NO. 60880

(TECHNICIAN) FORM CP-2/3