

TO: 1 031315 3-6  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,634-00-00  
NW SW SE, SEC. 5, T 19 S, R 42 W/E  
1000 feet from S section line  
2100 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4570

Lease Name Vern Well # 1-5

Operator: Samedan Oil Corporation  
Name & Address: 3817 NW Expressway, Ste. 1020  
Oklahoma City, OK 73112

County Greeley

Well Total Depth 5330 173.23 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well Gas Well Input Well SWD Well O&A x

Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 5 p.m. Day: 6 Month: 3 Year: 19 95

Plugging proposal received from Gary Fisher

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2505-35'

1st plug at 2500' with 50 sx cement, 2nd plug at 1650' with 80 sx cement,

3rd plug at 840' with 50 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:45 p.m. Day: 6 Month: 3 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 2500' with 50 sx cement, MAR 0 1995 03-09-95

2nd plug at 1650' with 80 sx cement,

3rd plug at 840' with 50 sx cement,

4th plug at 300' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

DATE 3-23-95

INV. NO. 42441

Signed Steve Durrant (TECHNICIAN)

EFFECTIVE DATE: 10-16-94  
DISTRICT # 1  
SWAT Yes No

State of Kansas  
NOTICE OF INTENTION TO DRILL 071-20,634-0700  
Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Expected Spud Date 10 25 1994  
month day year

Section NW SW SE Sec 5 Twp 19 S. Rg 42 East West

OPERATOR: License # 04570  
Name: Samedan Oil Corporation  
Address: Ste. 1020, 3817 N.W. Expressway  
City/State/Zip: Oklahoma City, Oklahoma 73112  
Contact Person: Debbie Kerr  
Phone: (405) 942-8707

1000' feet from South / North Line of Section  
2100' feet from East / West Line of Section  
IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License # ADVISE K.C.C. WHEN READY  
Name: Aberkrombs / Aug 4

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Greeley  
Lease Name: Vern Well #: 1-5  
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:  
XX Oil ... Enh Rec ... Infield ... Mud Rotary  
XX Gas ... Storage ... Pool Ext. ... Air Rotary  
... OGW ... Disposal ... Wildcat ... Cable  
... Seismic: ... # of Holes ... Other

Is this a Prestrat/Spaced Field? yes X no  
Target Formation(s): Morrow  
Nearest lease or unit boundary: 1000'  
Ground Surface Elevation: 3818' feet MSL

If OGW: old well information as follows:  
Operator: ...  
Well Name: ...  
Comp. Date: ... Old Total Depth

Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 80' 140'  
Depth to bottom of usable water: 1700' 1550'

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:  
Bottom Hole Location: Exp. 4/11/95

Surface Pipe by Alternate: 1 X 2 (1000) 200  
Length of Surface Pipe Planned to be set: (1000) 200  
Length of Conductor pipe required: None  
Projected Total Depth: 5600'  
Formation at Total Depth: Mississippian

Water Source for Drilling Operations: ... well ... farm pond X ... other  
O&R Permit #: NA  
Will Cores Be Taken? yes X no

If yes, proposed zone:  
200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-1106

RECEIVED  
OCT 17 1994  
STATE CORPORATION COMMISSION

Pusher Gary Fisher  
SPUD DATE 8/25/95 INIT. SD  
LENGTH SURFACE PLANNED 275'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 3/4 @ 298 CONDUCTOR  
ANHYDRITE T-2505 B-2535 ELEVATION  
TD 5330 FORMATION  
RAN PIPE @ DV TOOL ALT II DONE  
SX SX Y N  
Arbuckle Plug @ Ft. W/ SX  
Hng./Council @ Ft. W/ SX  
1 Anhydrite Base @ 2500 Ft. W/ 50 SX  
2 1/2 Base Anyh. @ 1650 Ft. W/ 80 SX  
3 1/2, 1/2 Plug @ 840 Ft. W/ 50 SX  
4 Bottom Surface @ 300 Ft. W/ 40 SX  
5 40' Plug @ 42 Ft. W/ 10 SX  
RAT HOLE CIRC/W/S SX MOUSE HOLE W/ SX  
WATER WELL SX (Irr. Well) Pond  
TECHNICIAN SD DATE 3/3/95 Hauling  
TYPE OF CEMENT 60/40 Pce 60/10-114-C.C.  
STARTING TIME 5:00 (AM/PM) DATE 3-6-95  
COMPLETION TIME 8:45 (AM/PM) DATE 3-6-95  
CEMENT COMPANY McLean