

10-10 12<sup>2</sup> R

1 031113

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 071-20,523-00-00

App. SW SE SE, SEC. 2, T 19 S, R 43 W/EX  
330 feet from S section line  
700 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Schmidt Well # 1-2

Operator: Amoco Production Company

County Greeley 171.30

Name & Address: P.O. Box 800, Rm. 1833  
Denver, CO 80201

Well Total Depth 5271 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 499

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 6033

Address 250 N. Water, #300, Wichita, KS 67202

Company to plug at: Hour: 6 p.m. Day: 10 Month: 10 Year: 19 90

Plugging proposal received from R.J. Prescott

(company name) Amoco Production Company (phone) 303-830-4009

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2600' with 50 sx cement, 2nd plug at 1650' with 80 sx cement,

3rd plug at 800' with 50 sx cement, 4th plug at 530' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 p.m. Day: 10 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2565' with 50 sx cement,

2nd plug at 1656' with 80 sx cement,

3rd plug at 800' with 50 sx cement,

4th plug at 530' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 10 sx cement,

7th plug to circulate mousehole with 5 sx cement. 10-25-90

Remarks: Used 60/40 Pozmix 6% gel by Dowell. (If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 10-30-90

INV. NO. 29784

10-10 JAN 10 1991

EFFECTIVE DATE: 9-25-90

FORM MUST BE TYPED  
FORM C-1 4/90

State of Kansas

071-20,523-~~0500~~

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 21, 1990  
month day year

App SW SE SE Sec 2 Twp 19 S, Rg 43 East West

OPERATOR: License # 5952  
Name: Amoco Production Company  
Address: P.O. Box 800, Rm. 1833  
City/State/Zip: Denver, CO 80201  
Contact Person: J.A. Victor  
Phone: 303/830-4009

330 feet from South line of Section  
700 feet from East line of Section  
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License # 6233 3098  
Name: Exeter Drilling

County: Greeley  
Lease Name: Schmidt Well #: 1-2  
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:  
 Oil ... Inj ... Infield  Mud Rotary  
 Gas ... Storage ... Pool Ext. ... Air Rotary  
 Oil ... Disposal  Wildcat ... Cable  
 Seismic; ... # of Holes

Is this a Prorated Field? ... yes  no  
Target Formation(s): Basal Upper Morrow  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 3854 feet MSL

If ~~OLD~~ old well information as follows:  
Operator: N/A  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth: \_\_\_\_\_

Domestic well within 330 feet: ... yes  no  
Municipal well within one mile: ... yes  no  
Depth to bottom of fresh water: 410'  
Depth to bottom of usable water: 1600'  
Surface Pipe by Alternate: ... 1  2  
Length of Surface Pipe Planned to be set: 500'

Directional, Deviated or Horizontal wellbore? ... yes  no  
If yes, total depth location: \_\_\_\_\_  
Exp. 3/20/91

Length of Conductor pipe required: \_\_\_\_\_  
Projected Total Depth: 5300'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well ... farm pond  other

DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: ... yes  no  
If yes, proposed zone: \_\_\_\_\_

AFFIDAVIT 200' Alt. II Req.

**\*ALT 2\***

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

523

Pusher Don Beil INIT. SB

SPUD DATE 9-1-90

LENGTH SURFACE PLANNED 499.62

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

2450 TOP-  
RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 5/8 @ 494 CONDUCTOR  
ANHYDRITE T- B- ELEVATION  
5271 FORMATION Morrow - 5000'

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Hug./Council @ 2505 Ft. W/ \_\_\_\_\_ SX

1 Anhydrite Base @ 2360 Ft. W/ 50 SX

2 1/2 Base Anyh. @ 1650 Ft. W/ 80 SX

3 1/2, 1/2 Plug @ 800 Ft. W/ 50 SX

4 Bottom Surface @ 530 Ft. W/ 40 SX

5 Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 10 SX MOUSE HOLE W/S SX

WATER WELL \_\_\_\_\_ SX (Irr. Well Pond Hauling)  
TECHNICIAN \_\_\_\_\_ DATE \_\_\_\_\_

TYPE OF CEMENT 60/40 60/40

STARTING TIME \_\_\_\_\_ (AM/PM) DATE \_\_\_\_\_

COMPLETION TIME 2:39 (AM/PM) DATE 10/10

CEMENT COMPANY Dowell  
2600 Upper Morrow -  
120 - 150 Cedar Hill 2890 -