

To: 1 031138 2-2  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

90' S & 90' W of  
API NUMBER 15-171-20,507-60-00  
SW NE NE, SEC. 31, T 18 S, R 34 W/R  
1080 feet from N & section line  
1080 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4779  
Operator: North American Resources Company  
Name & Address: 1700 Broadway, Ste. 508  
Denver, CO 80290

Lease Name Robinson Farms Well # 31-1  
County Scott 165.75  
Well Total Depth 5100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 422

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684  
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 8:30 p.m. Day: 1 Month: 2 Year: 19 97  
Plugging proposal received from Tony Martin  
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2420'  
1st plug at 2420' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,  
3rd plug at 750' with 40 sx cement, 4th plug at 450' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X  
Operations Completed: Hour: 12:30 a.m. Day: 2 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 2420' with 50 sx cement,  
2nd plug at 1320' with 80 sx cement,  
3rd plug at 750' with 40 sx cement,  
4th plug at 450' with 50 sx cement, RUP 02-26-97  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floeal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE FEB 14 1997  
INV. NO. 47578  
2-2

Signed Steve Durrant (TECHNICIAN)

EFFECTIVE DATE: 1-7-97

State of Kansas

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Spot 905 E 90' W OF

Expected Spud Date January, 10, 1997

SW NE NE Sec 31 Twp 18 S, Rg 34 East West

OPERATOR: License # 04779
Name: North American Resources Company
Address: 1700 Broadway, Suite #508
City/State/Zip: Denver, Colorado 80290
Contact Person: Mike Jensen
Phone: (303) 861-9183 Ext. 220

1080 feet from South (North) line of Section
1080 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Scott
Lease Name: Robinson Farms Well #: 31-1
Field Name: County Line
Is this a Prorated/Spaced Field? yes X no

CONTRACTOR: License #: 30684
Name: Abercrombie

Target Formation(s): MORROW
Nearest lease or unit boundary: 1080 feet
Ground Surface Elevation: 3155.8 feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 200 feet
Depth to bottom of usable water: 1250 feet 1380
Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 400 feet
Length of Conductor pipe required: None
Projected Total Depth: 5100 feet
Formation at Total Depth: Mississippian
Water Source for Drilling Operations: well farm pond X other

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext Air Rotary
OWWO Disposal X Wildcat Cable
Seismic # of Holes Other
If OWWO: old well information as follows:
Operator: N/A
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Will Cores Be Taken? yes X no
If yes, proposed zone:
220' Alt. II Req.

Exp. 7/2/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Tony Martin
SPUD DATE 1-22-97 INIT. mm
LENGTH SURFACE PLANNED 400'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 422 CONDUCTOR
ANHYDRITE T- 10 B- 2420 ELEVATION
TD 5100 FORMATION MISS
IRAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX Y N
Bug./Council @ Ft. W/ SX
Anhydrite Base @ 2420 Ft. W/ 50 SX
1/2 Base Anyh. @ 1320 Ft. W/ 80 SX
1/2, 1/2 Plug @ 750 Ft. W/ 40 SX
Bottom Surface @ 450 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN SD DATE 1-21-97
TYPE OF CEMENT 60/40 6/8 14 lbs a D
STARTING TIME 8:30 (AM/PM) DATE 1-1-97
COMPLETION TIME 12:30 (AM/PM) DATE 2-2-97
CEMENT COMPANY Allied