

1 050638

API NUMBER 15- 171-20,302-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 2, T 18 S, R 33 W
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Lease Name Carolyn Well # 1-2

Operator: R. J. Patrick Operating Company
Name & Address: P. O. Box 1314
Liberal, KS 67901

County Scott 157.69

Well Total Depth 4852 Mississippi feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1370

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor NRG Drilling, Inc. License Number 6666

Address Box 1157, Liberal, KS 67901

Company to plug at: Hour: 12:00 am Day: 19 Month: September Year: 19 85

Plugging proposal received from Jack Taylor

(company name) NRG (phone) 316-624-1818

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2098
Anhydrite 1360

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the bottom of the surface pipe with 50 sx cement

3rd plug at 700' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:00 am Day: 19 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2380' with 50 sx cement, 2nd plug at 1400' with 50
sx cement, 3rd plug at 700' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

OCT 15 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(if additional description is necessary, use BACK OF Form.)

INVOICED
I did not observe this plugging.

DATE 10-16-85

Signed Richard Lacey (TECHNICIAN) RL

REV. NO. 10617

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: September 10, 1985
month day year

API Number IS- 171-20,302-00-00

OPERATOR: License # 6528
Name R. J. Patrick Operating Company
Address P. O. Box 1314
City State Zip Liberal, Kansas 67901
Contact Person R. J. Patrick
Phone 316-624-8483

NE NE SW 1/4 Sec 2 Twp 18 S. Rge 33
 East
 West

2310 ft North from Southeast Corner of Section
2270 2970 ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6666
Name NRG Drilling, Inc.
City State Liberal, Ks.

Nearest lease or unit boundary line 330 feet
County Scott

Lease Name Carolyn Well# 1-2

Well Drilled For: Well Class: Type Equipment:
X Oil Swd Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
O.W.W.O. Expl Wildcat Cable

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

If O.W.W.O. add well info as follows:

Depth to Bottom of fresh water 1300 feet

Lowest usable water formation Cheyene

Depth to Bottom of usable water 1500 feet

Surface pipe by Alternate: 1 1/2 2 1/2

Surface pipe to be set 1500 feet

Conductor pipe if any required 30 feet

Ground surface elevation 2987 feet MSL

This Authorization Expires 3-3-85

Approved By 9-2-85

Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4850 feet
Projected Formation at TD Mississippi
Expected Producing Formations Kansas City & Morrow

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 8/30/85 Signature of Operator or Agent Mary Morgan Title Office Manager
SET 1500' @ 8 1/2" on 11/16/85
Form 4 84
WIA

PUSHER Jack Taylor -
TD 4852 FORMATION MISS
SURFACE PIPE 8 1/2 @ 1370 ANY -
ANHYDRITE 1360 ELEVATION 2987
STARTING TIME & DATE
COMPLETION TIME & DATE 9-19-85 - 2:00 AM.
1st PLUG @ 2380 FT. W/ 50 SX
2nd PLUG @ 1400 FT. W/ 50 SX
3rd PLUG @ 700 FT. W/ 40 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATION W/ 10 SX
MOUSE HOLE CIRCULATION W/ 10 SX
WATER SUPPLY WELL PLUGGED W/ TRANS TO STAND DOWN -
TECHNICIAN Hall. 6/4/82 -

RECEIVED
STATE CORRELATION COMMISSION
OCT 15 1985
CONSERVATION DIVISION
Wichita, Kansas