

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colcrado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89
RECEIVED
CONSERVATION COMMISSION

SEP 13 1991

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIV.
Wichita, Kansas

API NUMBER 15-171-20,430-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Stucky 'C' WELL NO. #1 WELL LOCATION C SE NW COUNTY Scott

SEC. 12 TWP. 19 SRGE. 31 (E) or (W) TOTAL DEPTH 4717' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 300.45 CEMENTED WITH 60-40 posmix-200 sx SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2300' w/50 sx; 2nd plug @ 1300' w/80 sx; 3rd plug @ 650' w/50 sx; 4th plug @ 320' w/50 sx; 5th plug @ 40' w/10 sx solid bridge; rathole 15 sx; 255 sx 60-40 posmix 6% gel 1/4# Flocel per sx on the 650' & 1300' plugs.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4:30 p.m. 8-9-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Tony Martin PHONE # (913) 743-5443

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS Abercrombie RTD, Inc. PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack R. Wharton
(Operator or Agent)