

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21954-00-00  
Spot: SENWSESW Sec/Twnshp/Rge: 4-14S-28W  
753 feet from S Section Line, 1815 feet from W Section Line  
Lease Name: TUSTIN Well #: L-4  
County: GOVE Total Vertical Depth: 4420 feet

Operator License No.: 3062  
Op Name: QUESTA ENERGY CORPORATION  
Address: PO BOX 50968  
AMARILLO, TX 79159

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 220        |             |          |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2011 12:00 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: JAY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS WitnessType: NONE  
Date/Time Plugging Completed: 11/28/2011 9:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st. Plug at 2065' w/25 sxs.  
2nd. Plug at 1052' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.


Perfs:

RECEIVED  
DEC 02 2011  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed   
(TECHNICIAN)

CM

Form CP-2/3

✓ 12/07/11

NOV 29 2011