

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-00145-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 14-29S-34W  
2440 feet from N Section Line, 2540 feet from W Section Line  
Lease Name: YOUNKER E R Well #: 1  
County: HASKELL Total Vertical Depth: 2740 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA.  
Address: 5205 N O CONNOR BLVD  
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2394		WITH 50 SX CMT
SURF	10.75	753		WITH 100 SX CMT
PROD	7	2511	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2011 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: TAG TOP OF FISH & RIH W/TBG TO TOP OF FISH & SPOT 50 SX CMT. PLUG AT 1500' WITH 50 SX CMT. PERFORATE 7" @ 700'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 11/11/2011 1:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

11/10/11: TAGGED TOP OF FISH @ 2405'. SET CIBP @ 2394' & PUMPED 50 SX CMT. PUMPED 100# HULLS & 100 SX CMT AT 1500'. SDON. 11/11/11: TAGGED TOP OF CMT AT 1276'. TESTED 7" CASING TO 800 PSI. HELD OK. PERFORATED 7" CASING AT 800' & CIRCULATED 420 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2716	2728		FT. RILEY
2680	2694		TOWANDA
2615	2656		WINFIELD
2548	2578		KRIDER
2525	2531		HERRINGTON

RECEIVED  
DEC 02 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\*USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed Steve Durrant  
(TECHNICIAN)

RECEIVED  
NOV 21 2011  
KCC DODGE CITY

Form CP-2/3

12/07/11