

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24174-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 18-14S-18W  
2961 feet from S Section Line, 2393 feet from E Section Line  
Lease Name: STATE OF KANSAS A Well #: 1  
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3285		
SURF	8.625	498	0	250 SX
PROD	4.5	3670	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/28/2011 2:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Revd. from: JODY SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 365 sxs 60/40 pozmix - 4% gel.  
PBTD 3657'. CIBP at 3285'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/28/2011 4:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 1365' - 1850' - 650'.  
Express Well Service RIH with tubing to 3019'.  
Swift Services rigged to tubing and mixed and pumped 150 sxs cement with 300# hulls mixed in.  
Pulled tubing to 800'. Swift Services rigged to tubing and pumped 120 sxs cement with 100# hulls mixed in to circulate cement up 4 1/2" casing and 8 5/8" casing shut in.  
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 20 sxs cement.  
Max. P.S.I. 250#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3436	3440		

RECEIVED  
DEC 12 2011  
12-2-11  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #21142.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)

CM

Form CP-2/3

12/06/11

NOV 29 2011