

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26219-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 17-13S-20W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HENMAN Well #: 1
County: ELLIS Total Vertical Depth: 3909 feet

Operator License No.: 33353
Op Name: WIESNER, TOM DBA TOM'S OIL
Address: 3108 E 13TH ST
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	221		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/18/2011 12:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Revd. from: TOM ENGEL Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 11/18/2011 9:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3853' w/25 sxs.
2nd. Plug at 1587' w/25 sxs.
3rd. Plug at 781' w/100 sxs.
4th. Plug at 271' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.,

Perfs:

RECEIVED
DEC 02 2011
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

12/07/11

NOV 21 2011