

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23372-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 1-14S-20W
4269 feet from S Section Line, 1806 feet from E Section Line
Lease Name: HERTEL Well #: 3-A
County: ELLIS Total Vertical Depth: 3940 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	249	0	160 SX
PROD	5.5	3940	0	600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/22/2011 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 475 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 11/22/2011 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3706' - pumped 150 sxs cement with 300# hulls.
Pulled tubing to 2400' - pumped 120 sxs cement with 100# hulls.
Pulled tubing to 1200' - pumped 110 sxs cement - cement circulated.
Tied onto backside - pumped 5 sxs cement. S.I.P. 300#.
Filled casing with 25 sxs cement - topped off.

Perfs:

Top	Bot	Thru	Comments
3886	3900		


RECEIVED
DEC 02 2011
12-2-11
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET 20428.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

12/06/11

NOV 23 2011