

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22300-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 34-30S-15W  
3630 feet from S Section Line, 4775 feet from E Section Line  
Lease Name: CROSS Well #: 1-34  
County: BARBER Total Vertical Depth: 4550 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3080		WITH 2 SX CMT
SURF	8.625	329		WITH 190 SX CMT
DVT		3234		
PROD	4.5	4545	2207	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2011 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 792-6702

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE  
Date/Time Plugging Completed: 11/30/2011 11:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

TOC @ 2980'. PBTD 4030' W/CIBP. 1ST PLUG SET CIBP @ 3080' WITH 2 SX CMT.  
2ND PLUG CUT CASING & PULL TO 920'. MIX & PUMP 15 SX GEL & 50 SX CMT.  
3RD PLUG PULL TO 360' & PUMP 50 SX CMT. 4TH PLUG PULL TO 40' & PUMP 20 SX  
CMT. CMT DROPPED. 11/30/11: TOPPED OFF WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4474	4484		
4452	4462		
3090	3097		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED  
DEC 05 2011  
KCC WICHITA

District: 01

RECEIVED  
DEC -1 2011  
KCC DODGE CITY

Signed Steve Durrant  
(TECHNICIAN)

Form CP-2/3  
12/06/11