

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00238-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 2-10S-23W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: GRIFFITH Well #: 3  
County: GRAHAM Total Vertical Depth: 4164 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290	0	150 SX
PROD	5.5	4163	0	500 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2011 1:00 PM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: BEREXCO, LLC (DENNIS) Company: BEREXCO LLC Phone: (785) 628-6101

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.  
Shoot perfs at 2070' - 1200' - 290'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2011 6:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3725' - pumped 13 sxs gel - followed with 75 sxs cement and 300# hulls.  
Pulled tubing out - shot perfs at 2070' - 1200' - 290'.  
Ran tubing back in to 2055' - pumped 150 sxs cement with 150# hulls.  
Pulled tubing to 1000' - pumped 85 sxs cement - good circulation.  
Pulled tubing out - pumped 90 sxs cement down 5 1/2" - circulated out backside - both full.


Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #35941

Plugged through: TBG

RECEIVED  
DEC 05 2011  
KCC WICHITA

District: 04

Signed   
(TECHNICIAN)

CM

Form CP-2/3

12/06/11

DEC 01 2011