

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01892-00-01
Spot: SWNENW Sec/Twnshp/Rge: 5-10S-19W
4290 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HAMEL Well #: 2
County: ROOKS Total Vertical Depth: 1960 feet

Operator License No.: 33937
Op Name: NEAL LAFON REALTY INC. DBA MERI
Address: 1475 WARD DR
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	170	0	w/125 sxs cmt
PROD	5.5	3756	0	w/unknown sxs cmt

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 11/29/2011 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRET HILDABRAND Company: MERIDIAN ENERGY, INC. Phone: (303) 688-4022

Proposed 11-29-2011 Ordered 50 sxs cement with 3.7 c.c.
Plugging 11-30-2011 Ordered 230 sxs 60/40 pozmix - 4% gel - 500# hulls.
Method: Lost hole at 1960' (salt section)

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2011 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

11-29-2011 - 9:00 A.M. - Ran tubing to 1960'.
Tagged - laid down two joints tubing at 1900'.
Allied pumped 50 sxs cement with 3.7 c.c.
Pulled tubing to 1000'. Shut in four hours.
2:00 P.M. Ran back tagged cement at 1788' - pulled two joints. Shut down.
11-30-2011 - Consolidated pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled to 669'. Pumped 75 sxs cement - circulated.
PTOH. Topped 5 1/2" casing off with 5 sxs cement - casing full.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RECEIVED

DEC 05 2011

KCC WICHITA

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

DEC 01 2011

Form CP-2/3

12/06/11