

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20272-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 12-10S-24W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GANO SE UNIT Well #: 3-2
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	203	0	175 SX
PROD	5.5	4039	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2011 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Squeezed at 3027' to 3058' with 150 sxs cement.
Shoot perfs at 2130' - 1300' - 200'.
Tubing lost in the hole. Spent two weeks with tools, pump, and power swivel trying to get down.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2011 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2401' - pumped 200 sxs neat cement - followed with 100 sxs cement with 400# hulls.
Pulled tubing to 1321' - pumped 75 sxs cement - good circulation.
Pulled tubing out - tied onto 5 1/2" - pumped 50 sxs cement - good circulation out backside - both full.

Perfs:

Top	Bot	Thru	Comments
3999	4004		LKC K
3976	3982		LKC J
3963	3967		LKC I
3941	3944		LKC H
3884	3888		LKC EFG
3808	3811		LKC A


Remarks: ALLIED CEMENTIN COMPANY-TICKET #38202.

Plugged through: TBG

RECEIVED
DEC 05 2011
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

(M)

Form CP-2/3

12/06/11

DEC 01 2011