

REC'D FROM DIST. 1
12/05/11 REVISED

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23097-00-00
Spot: E2NE Sec/Twnshp/Rge: 25-32S-13W
4005 feet from S Section Line, 775 feet from E Section Line
Lease Name: LONKERA Well #: 1
County: BARBER Total Vertical Depth: 5008 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450.

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4152		WITH 2 SX CMT
CIBP		4396		
CIBP		4460		
SURF	8.625	302		WITH 225 SX CMT
PROD	4.5	4789	2290	WITH 125 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/15/2011 3:00 PM
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.
Proposal Rcvd. from: MICHAEL PETERMANN Company: LB EXPLORATION Phone: (785) 252-8034

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 11/15/2011 4:55 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG SET CIBP @ 4152' & 2 SX CMT. 2ND PLUG AT 645' WITH 15 SX GEL & 50 SX CMT. 3RD PLUG AT 325' WITH 50 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4474	4490		MISSISSIPPI
4435	4438		MASSEY
4403	4410		MASSEY
4172	4177		LANSING

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

NOV 22 2011

KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

COPY

Form CP-2/3

✓ 12/06/11